SCHEDULI NG

HOW TO AVOID DELAY, ACCELERATION, IMPACT AND INEFFICIENCY

For Northwest Construction Consumer Council

Construction Conference & Exposition Washington State Convention & Trade Center Seattle, Washington

October 24, 2000 - 10:00 to 3:00

Presented By:

Steve Pinnell, PE - President, Pinnell Busch, Inc., Portland, OR Tony Bolstad - Project Services Manager, TIC, The Industrial Company NW Region, Tualatin, OR

Copyright [©] 2000 Pinnell♦ Busch, Inc.

OUTLINE OF PRESENTATION

HOW TO AVOID DELAY, ACCELERATION, IMPACT AND INEFFICIENCY

Morning - Scheduling

Overview Procedures Conflicting Objectives Differing Definitions WBS / Cost Coding Level of Detail Logic Resources Critical Path & Float Constraints & Targets

Afternoon - Scheduling Claims

Change Order Requests & Claims Time Impact Analysis vs. Would-Have-Been Schedules As-Planned & As-Built Schedules Detailed As-Builts & Other Tools Would-Have-Been Schedule Owner Defenses & Counterclaims Damages Inefficiency Negotiation

INDUSTRY TRENDS

CONSTRUCTION DISPUTE TRENDS:

- More Competition, Reduced Margins & Tighter Schedules
- Contractor Claims-Consciousness & Owner Risk-Avoidance
- Weakened Relations between Contractors and Subcontractors
- New Contract Forms Design/Build, CM/GC, & Build/Operate
- Changed Design Quality and Designer Responsibility
- Dispute Avoidance and Resolution Trends the '90s
- ♦ Partnering
- Dispute Management Programs

SCHEDULING TRENDS:

- Owner-Required CPM Specs
- Relatively Easy-To-Use Software on PC's
- Better Understanding of CPM
- Tighter Schedules
- Recognition of Schedule Importance & the Cost of Delays

Copyright [©] 2000 Pinnell♦ Busch, Inc.



SUGGESTED SCHEDULING SPECIFICATIONS

- CPM Schedule (not bar chart)
- Tabular Report with activity number, description, duration, early/late start and finish, logic (priors or successors), lag/leads, constraints, and float
- Timescale Logic Diagram or Connected Bar Chart
- Identify Subcontractor/Crew, Work Area, and Pay Item
- Specified Activity Durations and Number of Activities (maximum duration of 1 month, separate activities for each subcontractor, maximum detail with one activity per crew)
- Separate Activities for Procurement
- Sorts by Activity Number and Float/Early Start
- Preliminary Schedule at Pre-Construction Conference with details of first 60-days and summary to completion
- Complete Schedule within 60 days, Approval within 90
- Monthly Updates and Narrative with Pay Requests Updates w/actual start/finish dates, percent complete and days remaining.
- Revised Schedule When Delayed or Requested by Owner

Reduced Payment if Failure to Comply with Specs

SCHEDULE REVIEW AND APPROVAL PROCESS

- 1. Initial Review Upon Receipt Prior to Meeting
- 2. Joint Meeting with Contractor's Scheduler (and Superintendent)
 - Presentation by Contractor, Ask Questions, Take Notes
 - Review Critical Path in Sequence -- Logic, Crew, Qty ...
 - Check Work Quantities, Production Rates, & Durations
 - Check Critical Crew Chases (crane, equipment fleet, ...)
 - When Done, Brainstorm for Improvements
- 3. Approve at the Meeting or as soon as possible afterwards
- If Reject state exactly why and require re-submittal by a specific date.
 Offer to discuss to ensure you get what you need.

REASONABLE LOGIC AND ACTIVITY DURATION

- Missing logic ties
- Excess/duplicate logic ties
- Weather compatibility
- Crew chases that will control progress
- Excessive resource peaks and fluctuations
- Reasonable logic for efficiency
- Avoid crew stacking in limited work areas
- Reasonable durations (based on crew size/capacity)
- The effect of working under traffic
- Extended durations for startup or weather impact
- Contract-specified durations
- Check long-lead procurement times
- Overly tight schedules (multiple critical paths)
- Potential safety problems
- Conditions of railroad agreements
- Utility relocations by others
- Soil conditions, terrain, groundwater, etc.
- Contractor's capacity, approach, crew and work load

Copyright [©] 2000 Pinnell♦ Busch, Inc.

ADEQUATE LEVEL OF DETAIL

- Normal maximum activity duration of 1 month
- Number of activities for size and complexity of project
- Separate activities for each subcontractor
- ♦ Maximum level of detail: one activity per crew

OTHER ISSUES

- Anticipate potential delays and problems (complete weather-sensitive work before winter weather)
- Risk analysis of critical delays (push critical path activities into environmental no-work windows)
- Obtain expected crew sizes for critical activities and for each subcontractor
- Check for excess demands on owner's resources (inspection, surveying, etc.)
- Check on available access, public notice requirements, permit requirements

- Maintain Good Records record start-and-finish dates, delays and the reason why, crew sizes, etc.
- Enforce Contract Schedule Updating/Revision Requirements
- Meet to Discuss Delays, Impact, or Claims
- Promptly Respond to Questions or Notices
- Continue to Partner

MONTHLY UPDATES

The schedule reviewer should note and record the following information:

- Actual Start and Finish Dates
- Periods of Intermittent Progress with restricted or no work (and the reason)
- Days Remaining or Percent Complete of partially complete activities
- Minor Revisions to durations and logic
- **Correction of Logic** for out-of-sequence work
- Delays to the scheduled start of non-critical activities

INFORMATION TO BE RECORDED pg. 1

- Work started, completed, interrupted, in progress; its location and quantities
- Concrete pours where, how much
- Tests conducted and their results, if known
- Crew sizes, equipment and work by general contractor by trade
- Crew size, equipment and work by subcontractors
- ♦ Material delivery, on-site, being used and needed
- Contractor questions and responses given
- Directives to Contractor and action taken
- Summary of discussions with Contractor
- Delay or acceleration, the cause and impact
- Problems occurring, pending or developing; their impact and resolution
- ♦ Acceleration: directed, constructive, or contractor-initiated
- Changes in scheduled dates
- Changed conditions discovered or impacting work
- Accidents and their impact on work
- Restricted access and any impact

INFORMATION TO BE RECORDED pg. 2

- Damage to previously installed work
- Defective work being done, discovered, or reported
- Repairs to defective work, the effort expended and any impact on other work
- Extra work or protested work being done and any impact on other work
- Labor disputes, shortages, excess
- Problems with subcontractors
- Poor condition and control of subcontractors
- Changes in productivity, rate of progress, etc.
- Insufficient equipment capacity, poor operation, or inefficient layout
- Equipment delivery, removal, in use, on standby (not needed or need repair)
- Visitors to site
- Insufficient or inadequate labor or equipment
- Weather and its impact
- Other site conditions and impacts mud stream flow, traffic conditions
- Change order work, RFIs, etc. and their impact

Copyright [©] 2000 Pinnell♦ Busch, Inc.

SCHEDULING RECOMMENDATIONS For contractors

- 1. Train Key Personnel in scheduling, record keeping and claim avoidance
- 2. Train an In-house Scheduling Guru
- 3. Prepare Preliminary CPM Schedules for All Estimates
- 4. Submit and Discuss Schedule at Pre-Construction Meeting
- 5. Prepare Monthly Schedule Updates and Narratives
- 6. Tie Short-Interval Schedules to Project Schedule show Plan vs. Actual
- 7. Prepare Time Impact Analyses for Changes
- 8. Develop and Distribute a "Jobsite Overhead Cost Sheet"
- 9. Selectively Accelerate Low "Cost-Slope" Activities to lower total project costs

10. Maintain Better Records – superintendent's daily reports, RFIs, telcons, etc.

								PMS	30				Update:	05	Page	: 2
					CRITIC	L PA	TH SI	CHEDU	JLE - R	EPORT NO	1		Update d	ate:	318/	196
PROJEC	T FILE:C1516 RECORD: 5 SOR	T:Flo	at,E	arlyS	t PINNELL/BU	JSCH,	INC	• •••	PORTLAND	, OREGON	USA		Print: 1	2:14	04 JU	JN96
			DAY							E A	R L Y	L A	T E	FL-	DAY	x
NUM	ACTIVITY DESCRIPTION	DEP	DUR	PRIOR	ACTIVITIES	SUC	CESS	OR A	CTIVITIES	START	FINISH	START	FINISH	DAT	REM	COM
162	CERAMIC TILE	09	15	16156		171	180	175	177	5AUG96	23AUG96	12AUG96	30AUG96	5		
151	CONTINUE ELEC PNLS WIRE/TERMS	16	20	147		155				30JUL96	26AUG96	7AUG96	4SEP96	6		
155	ELEC GENERATOR SYSTEM	16	8	151		213				27AUG96	6SEP96	5SEP96	16SEP96	6		
103	MASONRY VENEER	04	5	101-5		107				27JUN96	3JUL96	9JUL96	15JUL96	7		
107	ROOFING SYS	07	15	101 1	03	161	121	109	110	5JUL96	25 JUL 96	16JUL96	5AUG96	7		
175	TRIM PLBG FIXTURES/TEST	15	10	162		177				26AUG96	9SEP96	5SEP96	18SEP96	7		
177	TLT PARTS & ACCYS	10	8	162 1	75	191				105EP96	19SEP96	19SEP96	30SEP96	7		
50	SITE UTILITIES AND FINISHES+		112	51H 8	9	H				A09MAY96	1600196	17JUN96	2800196	8	97	13
13	FABRICATE HVAC DUCTWORK	15	20	9		131				31MAY96	27JUN96	12JUN96	10JUL96	8		
52	UG ELEC MAIN FEED	16	12	51s2		54				A31MAY96	13JUN96	12JUN96	25 JUN96	8	10	10
54	RETAINING WALL FTGS	03	10	27\$2	53 52 10 51	55				14JUN96	27JUN96	26JUN96	10JUL96	8		
131	DUCTWORK INSTALLATION	15	30	31-4	13-4	163	171	133	135 145	24JUN96	5AUG96	5JUL96	15AUG96	8		
						132										
55	MASONRY RETAINING WALLS	04	10	54		57				28JUN96	12JUL96	11JUL96	24JUL96	8		



Copyright [©] 2000 Pinnell♦ Busch, Inc.









Copyright © 2000 Pinnell♦ Busch, Inc.

HOW TO VERIFY (or create) AN AS-PLANNED SCHEDULE

- 1. If No As-Planned Schedule Exists, Create One
 - 1. Base it on reasonable expectations at the start of work and actual progress to date.
 - 2. Document all assumptions, references, and computations.

2. If A Bar Chart, Convert It Into A CPM Network

- 1. Identify and draw relationship lines on the Bar Chart.
- 2. Add detail as required.
- 3. Computerize.

3. Plot The As-Planned Schedule As A Timescaled Network

For easier review and better understanding, plot the As-Planned Schedule as a Timescaled Network Diagram showing the activities scaled to a calendar and the relationships shown between activities.

4. Verify Adequacy And Accuracy, And Modify If Required

- 1. Examine the job logic, activity durations, available resources, etc.
- 2. Add missing activities and relationships, show overlapping activities or intermittent progress, and correct patent (obvious) errors.
- 3. If necessary, modify the As-Planned Schedule for comparison with the As-Built.

					S		JUN97					L
			DAY	START	FINISH	26	05	09	16	23	30	C
	NUMBER	ACTIVITY DESCRIPTION	DUR	DATE	DATE	н.	м	м.	м.	м.	Μ.	<u>н</u> ,
	1	Notice to Proceed (23MAY97)	00	23MAY97								
	2	Hobilization	5	23MAY97	27MAY97			1				
	3	Demo Kitchen	5	23MAY97	30HAY97	1 KXXX	×	<u>}</u>				
	6	General Conditions	67	23MAY97	27AUG97	$\sqrt{8}$	XXXXXX	*****	*****	XXXXX	XXXX	XXX
	9	Structural Steel Deliver	12	23MAY97	10JUN97							i
	15	Wood Doors/Frames Del	2	28MAY97	29MAY97	12-0		1	= -	+	÷	
	5	Asbestos Removal	2	2JUN97	3JUN97		X					
	4	Demo CMU Wall	5	4JUN97	10JUN97	\langle	1 2	xxxy	ł (
	10	Structural Steel Erection	4	11JUN97	16JUN97	\backslash	i		<u> </u>			
	11	Lumber/Plywood/Material Del	s	11JUN97	12JUN97	4_	- + -	+	71)			
	12	Rough Carpentry	5	11JUN97	17JUN97		1	E	-			
	8	Conc. Saw/Drilling	2	17JUN97	18JUN97				\boxtimes	1		
	17	Metal Framing	5	19JUN97	25JUN97					boxxy	4	1
	16	Install Wood Doors/Frame	2	26JUN97	27JUN97					(('		1
	23	Rough-In Plumbing	12	26JUN97	14JUL97	6.4					0000	∞
	25	Rough-In HVAC	12	26JUN97	14JUL97					X	5	
HTGI	22	Rough-In Fire Prot.	3	30JUN97	2JUL97						Ц	
р. р	27	Rough-In Electical	13	2JUL97	21JUL97					62		\boxtimes

Copyright [©] 2000 Pinnell♦ Busch, Inc.

HOW TO VERIFY (or create) AN AS-BUILT SCHEDULE

1. If No As-Built Activity Exists, Create One

- 1. Base it on actual progress as noted in the job records.
- 2. If necessary, create a Detailed As-Built Schedule and condense it to the same level of detail as the As-Planned.

2. Verify The Accuracy Of The As-Built Schedule Updates

- 1. Examine the records to determine if the schedule was updated regularly.
- 2. If Short-Interval Schedules exist, compare them with the As-Built Schedule.
- 3. Check the accuracy of the start and finish dates and job logic.
- 4. If significant shortcomings exist, check all critical and near-critical activities.

3. Modify The As-Built Schedule, If Necessary

- 1. Correct for errors and logic changes, add missing activities and detail (if required.)
- 2. Use the Short Interval Schedules, the daily field reports, and other records.
- 3. If necessary, create a Detailed As-Built Schedule and then condense it to be compatible and with the same level of detail as the As-Planned Schedule.



HTGP – Pg. 313, Fig. 10.27

Copyright [©] 2000 Pinnell♦ Busch, Inc.



Copyright © 2000 Pinnell♦ Busch, Inc.

DETAILED AS-BUILTS Advantages And Disadvantages

For Analysis

- Explains apparent contractor errors
- Identifies additional issues
- Can generate productivity rates and damages
- Offers convenient display and access to other data
- Provides information for issue analyses and reports
- Provides all the above simultaneously

For Presentation

- Easier to understand
- Refutes alleged concurrent delay
- Allows quick response to unanticipated questions
- Establishes credibility
- Provides a foundation for conclusions
- Intimidates opposing witnesses

HOW TO PREPARE A "WOULD-HAVE-BEEN, BUT FOR. . . "SCHEDULE

- 1. Plot As-Planned vs. As-Built Comparison Bar Chart evaluate differences
- 2. Review Time Impact Analyses of individual delays (if existing)
- 3. Examine the Detailed As-Built Schedule if one was created
- 4. Review Issue Analyses and Chronological Summary Notes
- 5. Create an ELIPSE Schedule integrating RFIs, extra work, the schedule
- 6. Look at Labor & Equipment Use
- 7. Optionally, Prepare What-If Analyses and Computer Simulations
- 8. Create the Would-Have-Been Schedule:
 - One activity at a time, from the beginning
 - Based on the contractor's intent as evidenced by the as-planned schedule and subsequent documents (correspondence, schedule updates, etc.)
 - Adjusting the job logic, when appropriate, to what the contractor probably would have done under the circumstances
 - Using actual durations for un-impacted activities, after adjusting for the working conditions when the work would have been done.
 - Using computed durations for impacted activities, based on an analysis of planned duration, actual duration, actual vs. would-have-been working conditions, crew size and productivity rates, etc.
- 9. Include Excusable but Non-Compensable Delays e.g. weather
- **10. Record Assumptions and Calculations**

Copyright [©] 2000 Pinnell♦ Busch, Inc.

31	Notice to Proceed	00	A 3JAN96		8			
3	General Conditions	71	A 3JAN96	10APR96				
4	Mobilization	8	A 3JAN96	A13JAN96				
5	Demolition	9	A 3JAN96	A15JAN96	2000000000			
6	Earthwork	18	A 7JAN96	7FEB96				
10	Lumber Deliver	3	A15JAN96	A17JAN96	8000			
7	Concrete/Building	5	A20JAN96	6FEB96				
28	Plumbing Rough-in	8	2FEB96	13FEB96				
13	Manufactured Wood Trusses	1	6FEB96	6FEB96		8		
12	Rough Carpentry	13	A28JAN96	20FEB96				200
19	Roofing	1	9FEB96	9FEB96		8		
22	Vinyl Windows	1	12FEB96	12FEB96		0		
20	Flashing & Sheetmetal	1	13FEB96	13FEB96	-	0		
30	Electrical Rough-in	6	A29JAN96	19FEB96				
8	Concrete/Sidewalks	3	14FEB96	16FEB96				
11	Vinyl Siding	2	14FEB96	15FEB96				
17	Insulation/Walls	1	20FEB96	20FEB96		8		
9	Structural Steel Handrails	5	21FEB96	27FEB96				
23	Gypsum Wallboard	10	22FEB96	6MAR96				
26	Painting	10	7MAR96	20MAR96				
24	Floor Covering/Resilient	3	14MAR96	18MAR96				
21	Doors/Frames/Hardware	1	18MAR96	18MAR96			0	
14	Finish Carpentry	5	21MAR96	27MAR96		-		
15	Millwork Materials	1	21MAR96	21MAR96			8	
16	Cabinetry	5	21MAR96	27MAR96			888888	
18	Insulation/Ceiling	1	21MAR96	21MAR96			0	
	Toilet Accessories	1	28MAR96	28MAR96			_ 0	
29	Plumbing Finish	3	28MAR96	1APR96			822	8
31	Electrical Finish	2	2APR96	3APR96				222
25	Floor Covering/Carpeting	5	4APR96	10APR96				
32	Completion	000		10APR96	_		0	8

Copyright [©] 2000 Pinnell♦ Busch, Inc.

NUMBER ACTIVITY DESCRIPTION	10	RENO	RK C	DEP RES	C051 C00E	DATE	START D WORK	FINISH	ALIG 95	90	69 2		0CT 07	NDY	DEC		JAN 06	FEB 03	RAR S0	APR	HAT	, mr	1
300 PLUMBING RI ML	26	1 30	18 1	164	-		AL 2SEPSI	129KAY92			'n	0000		ANNO TO	www	2002	mm	anna	min		******		
11 07 RET 4019 PLUNBING RE KITCHEN		8 30	18 1	154	CD	28AU091	A1 60CT91	A230CT91	1.12	۵			223										
1564 AFI 4032 AI PLOG CARRIER		2 30	18 1	154	DE	95EP91	AI SEPSI	A205EP91		50.	۵											<i>.</i>	- 1
1555 AFI 4033: HOSE BIB FINISH		1 30	18 1	154	00	105EP91	AL 25EPQ	AL 2SEPOL			4												- 1
1559 RFI 4030 PLUMBING WALL DINEKS	1	6 30		154	DE	1 35EP91	A20SEPSI	42556791			۵	22											- 1
1571 AFT 4039 PLUMBING WALL DINENS		1 30	18 1	154	DE	1355791					۵												- 1
1583 AFT 4058 MENS BAR WALL LAYOUT		1 30	18 1	154	Œ	1100791	A1 60CT91	A1 60CT91					A 0										
1001 AST 1 & KITCHEN PLUNGING HODIF	25	7 30	18 1	154		1900791	A						۵										- 1
1156 RFI 4084 KITCHEN PLUBHING RELI	C	2 30	18 1	154	DE	710191	AL SHOVEL	AS 4NOVEL						A 8									- 1
1157 RFI MOBS GLULAN S. D. PIPING		2 30	18 1	154	Æ	710191	AL BHOYSI	AS SHOWER						Δ 0									- 1
1159 RFI 4092 INTER FRAME/PLN AI		1 30	18 1	154		1240491	AS 2NOVES	AS 2NOVES						1									- 1
1193 RFI 4135 PLSG & SERY BAR ATHS		5 30	18 1	154	Æ	406091	A1 90EC91	A23DEC91							۵								- 1
1195 RFI #139 N F BEAN RH 175	1.6	1 30	18 1	154	Æ	606091	AS 7DEC91	A1 7DEC91							Δ	1							- 1
1625 RF1 #140: REDO ROUGHIN URINALS		2 30	18 1	154	Œ	60EC91	AL TOECOL	AS BOECRE							۵	B							- 1
1354 RF1 #154: FLR DRAIN STHEN 142/2	3	7 30	18 1	154	DU	1506091	AL IFEB92	A1 7FEB92								Δ		22					- 1
1230 RFI 4185: PLUMBING VENT RN 158		2 30	18 1	154	00	1906091	A 2.JANS2	A JUNER								4	8						
1644 RET 4185 LOCATE FLOOR DRAINS		3 30	18 1	154 0	DU	2406091	AI SJANSE	A17JANS2								۵							- 1
1648 RFT #210: GAS PIPING SIZE KITO	×	1 30	18 1	154 0	Æ	15JAN92	A21 JAN92	API JANS2									A 1						- 1
1010 ASI 33 KITCHEN MODIFICATIONS		6 30	18 1	154 0	Œ	22JAN92	AL 7 JAN92	A22JANG2									22						
1662 RF1 #241: NEED DINENS WAIT STN		1 30	18 1	154 0	00	SEMME IE	A 7FEB92	A 7FEB92										4 1					·
1306 RFI #250: MOYE F. S. IN RH 128		3 30	18 1	154 0	æ	SFEB92	A1 9FE892	A21FEBS2										A 0					
1495 81-0043: ROOF YENT	1	1 30	18 1	ISA (00	7FEB92	AL SFEB92	A11FEBS2										41					
1453 ACCO 028 ADD SIRIR RM 153		1 30	18 1	154 0	DU	19FE892	A22APR92	ASSAMASS										۵					
1052 ASI 49 CERAMIC TILE	3	1 30	18 1	154		27144792	AS SHANDS	A10.AM92												Δ	7777	7777	
1454 81-0054: DENO & REPAIR KIT MAL	4	1 30	18 1	154 0	œ	SAPR92	A SAPRS2	A SAPASS							4					4			
1745 REI #377: ADO CR VALVE WTR SPLT	r	2 30	18 1	154 0	00	444792	AL ANAY92	A154AY92													A 0		- 1
1768 RFI #396: ALEXANDER NEWS BK BAI	8	1 30	18 1	154 0	20	1 SHAY92	A22MAY92	A22MAT92													41		
1785 RFI #412 KITCHEN BACKFLOW PRVS	N :	1 30	18 1	154 0	20	BJUN92	AS 2 JUN92	A12.0492		-		100			_							41	. B
341 PLUNEDIG RE 2ND	12	7 30	10 1	154									1		٩	1		a		(C-7) (C-7)			
1177 REI 4111: PLBG WTR HTR DESIGN	1	5 30	10 1	154 0	æ																		
1366 RFI #134: HVAC BOILER RM WALL	1	9 30	IC I	15A (æ																		
1671 RFI 4274: ADD HEHBR BOILR FH21	9	3 30	IC 1	154 0	Æ	1		1															1
333 DELTA FIRE LL RI	7	4 33	3 1	150			1																
1169 PFI 4101: FP HVAC/ELEC CONFLIC	1	3 33	3 1	150 1	æ																		
1017 AST 38 MECHANICAL	7	5 33	3 1	150					1														

STRUCTURAL	156	A28MAR94	A 3NOV94			-		VIII	1111	777	1111	1111	7747	77777	7770	mm	2274	1111	11111	4mm	1114
Franing	156	A28HAR94	A 3NOV94	- 1				TIT	7777	mh	7117	200	min	um	Th	77777	2002	1111	11111	min	
structural carpentry labor	34			8540		1	1 9	. P 1	6 222	2º 50	103 10	3 32 4	st st a	1º 12' 1	10 13	308 248	30 3	P 49 3	3 48 A	2 9 24	4° 4
wall plywood & sheeting labor	21			928		1		1	0	\$ 24	\$ \$	12 1	\$ 4 1	2 .	• 1	\$ \$	\$ 1	1 5 .0	3 8 6	4	1
Erect Trusses	58	A22APR94	A14.JUL94			1		1		221	TZZ	7777	1111	1111	ZZZ	22	s 1			Ĩ.	1
erect structural steel labor	14			308		-		. •		\$ 9		2.	9 0 0	\$ 1	0 9	3	*				
Receive & Set Steel Beam	1	A SHAY94	A GHAY94	1							۵										'
Roof Plywood Sheathing	85	A1 2HAY94	A12SEP94	1							e	m	m	772		2777		1111	11111	1722	
roof plywood labor	16			894							10	100	2 . 1 .	0, °4		2.8	8 9	10 0	33	9 20	
Trusses at Gym	4	A 2AUG94	A 5AUG94														1	2		1	
Framing # Locker Room	3	A155EP94	A19SEP94					1					i.		- 2						
Build Playshed	. 11	A15SEP94	A295EP94						_						- 1					1 12	
FINISH CARPENTRY	107	A30JUN94	A 1DEC94		1	- 9				1					t	77777	777	1111	min	hm	mi
Finish Carpentry	107	A30JUN94	A SDEC94					1		1			1		et	7772	đ	77777	77777	Ann	7777
finish carpentry labor	19			494				1		1			1		- 27	1 3	2	10	\$ \$ P	1 32 10	2 9
MDO at Gym	6	A22SEP94	A29SEP94	- 1				1		1			1		1		1			1	EZZI
Door Frames & Jambs	66	A28JU.94	A290CT94										- <u>-</u>		- 1		d	1111	7777	10	
door frames &)ambs -labor	8	{		126						1			1		1		.4	\$ 3	6 6	1	1
Hollow Hetal Doors	15	A 1SEP94	A22SEP94																	41111	21.
hollow metal doors labor	3			80																9 0 5	1.1
FINISH HARDWARE	68	A25AUG94	A 1DEC94		1	E		E		1			3		1				22	iquit	
finish hardware labor	13			794				-	-							6			*	1° 1° 1°	\$\$
MOVE-IN	10	A 31 AUG94	A1 4SEP94		1	1			1200	1					1		i.	8 8	_	ATTA	1
CLEAN UP & PUNCHLIST	1 49	AL GHAY94	A1 SDEC94	i	1	1		1		1	C C	7777	TAT	222	1		1		1/027.2	Q77777	2224
clean-up & punch list labor	20			284		-+-		9		1 3	8	2 2	0 3 0	1.2	-	¥2. 9		0		0 0 0	9
FINAL COMPLETION GRAND TOTAL	000		A1 30EC94	18278	1 3	s .	in the s	3 d 4	pr .39	611 7th	68 ⁸ 11	3 138 1	r sh e	* & ,	yr yf	3 ¹⁰ 6 ³⁹	40° -3	6 49 49	° 4² 4°	\$\$ \$\$ \$\$	8 4
	L				1	1				-			L		l	1000	1			L	
											C1 40	8 XS-4	LANNED	VS. AS-	BUILT	SCHEDULE	COMPA	MISON	Plot date	2 Date: 2 010EC96	95EP95 20: 30

MBER	ACTIVITY DESCRIPTION	DAY WORK DEP OUR AREA RES	START DATE	FINDSH NOV DATE 11 ST	EC JAN FEB 10 2 06 07 02	AR APR MA1 2 .06 .04	Y JUN JUL AU 01 05 03	G SEP OCT NOT 07 05 02	01C J	AN FEE WAR AP 4 01 01 05	R NAY	JUN JUL AUG 07 05 02	3EP 0CT .06 .04	NOV DEC 01 06	1994 JAN 92
					1	т	OWE	>	1					8	
					1		OWE		1					1	
					1 month		Start As	-Planned	Start	Actual				8	t.
Sec.							∠ Mechani	cal Work	Mecha	anical Work				1	
-2213	Pour Woll Figs @ Tower - Bant	24 TONB MOR	A21JAN92	A21FE892	stars in case of		1	1	-					8	
2230	Pour Grade Beans # Tower - Ban	10 TOWE MOR	A24FEB92	A GHAR92	Lines and				1					3 -	
2313	Pour ran Walls @ Tower - Bent	18 TOWN MOR	A 9MAR92	A 1APR92	1				13	SOG 9 month	s delay	1		8	i
-0000	Pour colls @ Towar - Bast	17 TONE MOR	A TOPEB92	A 3MAR92				1 million 1	1	+2 mon	ths late	schedule		8	i.
-3363	Pour Concrete Stolrs & Town -	3 7048 304	A280EF92	A2106092	1000	1 10 10 10 10								8	1
-3413	Four Int Shearwalts p # To	1 TOWE WOR	13044992	A30MAP92	12119	1			1					8	1.
-2313	Pour Fdn Wolls & Towar - Magz	22 TOWN MOR	A TALAPOT	A LAPREZ		-								8	
-0113	Pour Cols @ Towar - Mezz	17 TOWN MOR	A TOFEB92	A 3MAR92	A DECK				1						1
-3363	Pour Concrete Stairs # Tower -	5 TOWN JOH	A 2FEB93	A BFEBRO	1000	1			1					8	
-0413	Pour Int Shearwails p . To	1 TOWN MOR	A30MAR92	A30MAR92		1									
-3113	Pour Cole p 2 @ Tower - 1st	14 TOW1 MOR	A26MAY92	A12.0NP2	1 10		The second se							8	1
-3313	Pour Str Slob p 2 @ Tower -	1 TOWS JOH	A SMAT92	A TMAY92		1			1	-				8	
-3363	Pour Concrete Stairs @ Tower -	7 T091 J0H	A BFEBRO	A14FE393	1				i					22	1
-30/3	Pour Ext Gonc Wollis p 2 # To	3 TOW1 MOR	A 12DEC92	A150EC92	1		ALC: NOT THE OWNER.							8	1
-3413	hour int shearwoils p 2 # Te	1 TOW1 MOR	A29MAY92	A29MAY92		L	A CONTRACTOR		1						1
1010	Pour cola p 6 @ lower - 2nd	15 TON2 MOR	A BJU.920	A28.JUL92		A 14				-					1
-3363	Pour pur sido p 6 e lover -	1 TOW2 JOH	A26-JUN92 1	A25JUN92	5	1.1	1 666								1
-3373	Pour Fut Come Walls a 6 8 To	1 7782 400	AT A DELET	LOK E BIDD		308 3			1	-				8	
-0413	Pour Int Shearwails a 6 8 To	3 1092 408	A R.58.92	10.18.02		1000		A CONTRACTOR OF						8	
-3113	Four Cole p 12 @ Temar - 3rd	11 TOYO MOR	A 500192	1900792	1		10				-			B	1
-3313	Pour Str Slab p 12 8 Tower -	1 TOWS JOH	A 7AU092	78,092			10 N	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			· ·			2	
-3363	Pour Concrete Stalrs & Tower -	1 TOWD JOH	A PULLY A	SEMILE A	1		A 1	1.0.2	· ·			0		10	
-3373	Pour Ext Conc Wolls p 12 # Te	14 TOWO MOR	A 740092	L26AU092	1	1000		10 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1						
-3413	Pour Int Shearwalls p 12 # To	1 TOWN MOR	AT ISEP92	119EP92	1	100		1000	1			•		8	1
-3113	Pour Cale p 20 • Tower - 4th	11 TOWA MOR	A16N0V92 A	L30N0V92	1		2		1			a		8	1
-3313	Pour Str Slob p 20 @ Tewar -	1 TOW4 JOH	A 2MOV92 A	210192								1000		8	1
-3363	Pour Concrete Stalrs @ Tower -	1 TOWA JOH	A 9,0093 A	SEMLL 9			1							8	19
-3373	Four Ext Conc Walls p 20 @ Te	7 TOWA MOR	A11N0V92 /	1960/92										8	
.0113	Pour ant sheared is p 20 e 16	2 7084 MON	A13NQV92 A	16/0/92			No. 1 Contraction					_		1	
-0313	Pour Str Steh n 28 @ Tower -	1 1085 304	1406192	S-JARYS			1111		100			8			
0060	Pour Concrete Stolrs & Tower -	1 TONS JOH	22.3583	22.1.8921	1		1.1			← As-Built		4 Sta	ire	8	
0373	Pour Ext Conc Walls p 28 # To	3 TOWS MOR	12 10E092	230EC92	1			← Stairs				1		8	
3413	Pour Int Shearwails p 28 # To	1 TONS MOR	SJARRY A	SJANRO	1		1000	a cours	1					8	
3113	Pour Cols p 37 @ Tower - 6th	5 TONS MOR	A CRIALA	CEMALE A			100	12	1	10				8	1
-0313	Pour Str Slab p 37 # Tower -	1 T095 J0H	15JAN93 A	15JAN93	1			2	6	1		1		8	1
3363	Pour Concrete Stalrs @ Tower -	1 1086 30H	6JJ.93	630.93		As-Plan	nned 7		1			1		1	1
3373	Pour Ext Conc Walls p 37 # To	4 TOHS MOR	20JAN93	25JAN93	1				1	X				8	1
-3413	Pour Int Stearwalls p 37 8 To	7 TOWS MOR	A CRIMELICS	CRIMN93					-	68		-		8	
3313	Hour str Slob p 41 @ Tower -	1 TOW7 JOH	25/EB93 A	25/1093	1				1	and the second				8	
1075	Form Delf Mour Fet Comer-	10 1097 104.0	A COLLO A	26.8.8.93	1				1	Section Section	-	100		1	
3413	Pour Int Descentia o at a To	15 TOWT HON	TRANSIC A	La ratifica a	1			•	1					8	
3313	Pour Str Sick o 45 & Tower -	1 1087 1047	1.1.807 A	1.0000	1			0		(8	
-0412	Pour Int Shearwalls p 45 8 Ta	1 TONE WHO	T344793 A	1168/25	1			1 .	+ 10					8	
10000					1			- 8	-1/2 moi	nthŝ	,			1000	
-	TATION BILL AT AN ANALY				1				1					8	
COLOR DO TO	a lete	Fielen									1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.		enderstation and the	States and states	



Copyright [©] 2000 Pinnell♦ Busch, Inc.

C1130 Would have been, but for PROJECT FILE:C1130 RECORD:	PMS80 SCHEDULE COMPARISON - REPORT NO 11 15 SORT:Activity Numb PINNELL/BUSCH, INC PORTLAND, OR	Update: Update da Print da	: 15 Page: ate: 28AUG9 ate: 24SEP9
NUM BER ACTIVITY DESCRIPTION	WORK <as-planned schedule=""> <would-have-been schedule=""> < AREA DUR EARLY ST EARLY FN DUR EARLY ST EARLY FN REMARKS (Rainfall)</would-have-been></as-planned>	CHANO	ES> ES EF
1018 PLUMBING UNDERGROUND	A 3 14SEP90 18SEP90 3 7SEP90 11SEP90 1d .03 .	0	-5 -5
1024 BACKFILL This activity was in in September when no r area caused by the thr This was probably over to 2Nov, but 6 of thos addition to the substa	A 3 80CT90 100CT90 4 25SEP90 28SEP90 2d .09 creased from 3 to 4 days, in spite of being scheduled ain fell. This was to adjust for the larger excavated ee sanitary sewer line taps (a change to the contract). Ly conservative. The actual work took 8 days from 240ct e days experienced rain with a total of 1.59" in intial rains before work started.	1	-9 -8
1026 CMU - 1ST FLOOR	A 3 110CT90 150CT90 3 10CT90 30CT90 3d1.43	0	-8 -8



Copyright [©] 2000 Pinnell♦ Busch, Inc.

			~	3-P	LANN	IED V	s. A3-	bui	LI 34	HEDI	ILE	LOM	PAR	130	N					
		ſ									1996									_
			M	AY			JU	NE				JULY	-		1	AUC	GUST		SEPTE	MBER
		_	1111100860	2.1.2		88888	11111	2222	石橋道路に	858888	882:2	的物口物物	***	***	53885	882223	22228878	***	888888	101108
	START	COMPLETE	NTWITHTHTWITH	W T.W	TENTWO	THTWR	FMTWTF	NTWIT	FMTWT	NTWOF	NTWRF	MTWTF	HTWT	FWTW	THENTW	THENTWI	PNTWR	FMTWT	FNTWTF	M T W Th F
AWARD																				
Contract	6-May	23-May	Contract Award	ed	Contract	Signed &	Returned													
Pre-Con Mtg	29-May	29-May			P	re-Constr	uction Mee	ting												
NTP	3-Jun	3-Jun				Notic	e To Proce	ed				2				1			2	
Excavation F & P Foundation REVISED AS Mobilize Setup Trailers Demolition	25-Jun 2-Jul PLA1 18-Jun 21-Jun 28-Jun	1-Jul 15-Jul 15-Jul 20-Jun 27-Jun 24-Jun)						Mobilize	Excava	ers	Form 8	A Pour F	Foundat	lon		*			
Excavation	20-Jun	24-Jun			-	+	-		-		E	xcavation	1			-	-			
F & P Foundation	12-14	25-JU				1								Form 8	Pour Fo	undation				
AS-BUILT			ſ											+	13	4 MONT	HS DELA	Y		→
Mobilize	18-Jul	29-Jul		1							Mol	bilize	÷.							
Setup Trailers	20-Jun	20-Jun					Setup Tr	ailers												
Excavation	31-Jul	27-Aug											Excav	ation		13 1				
And the second s													Earm	& Pour	Foundat	ion				

OWNER DEFENSES AND COUNTERCLAIMS

- Lack of Entitlement disputed contract interpretation or other failure to prove the contract or contract law entitles the contractor to extra payment or time extension
- Concurrent Delay due to weather delays, contractor error in prosecuting other activities, etc.
- Failure to Re-Sequence overlap relationships, expand level of detail, break non-essential logic links, re-sequence activities, add labor or equipment to eliminate resource constraints, etc.
- Faulty Scheduling poor or impractical as-planned schedule, overly optimistic as-planned activity durations, inaccurate or insufficiently detailed as-built schedule, incorrect or inadequately supported would-have-been schedule logic and durations
- Erroneous Analysis lack of causation, improper allocation of delay, unsupported computation of damages
- Liquidated or Consequential Damages for non-excusable delays and consequential delays to repair defective work
- Defective Work out-of-spec work product



Copyright [©] 2000 Pinnell♦ Busch, Inc.

TYPES OF DAMAGES

Direct Cost of Extra Work -- From a change resulting in a project that is different and more costly.

Labor

Equipment

Materials

Subcontract

- Small Tools & Expendables
- Mark-up

Impact from Change In Conditions -- under which the work is done, which can be:

- Inefficiency -- of labor, equipment and subcontract costs in performing original bid work.
- Additional Tasks -- not leading to a scope change in the project, such as access road.
- Additional Materials -- such as extra base rock to allow working on wet subgrades.

Delay -- causing the project to take longer or be done later, resulting in:

- Extended Overhead -- of jobsite and home office overhead
- Escalation -- in the unit costs of labor, materials, equipment use, or subcontract costs.
- Equipment Standby -- while waiting for a problem to be resolved.
- Demobilization and Remobilization -- due to delay and the need to return later.
- Extended Warranty -- and other cost due to delay
- Change In Conditions with Impact (inefficiency, additional tasks and/or materials use).
- Lost Profits -- for projects that could not be bid, due to delay. No markup added.

Acceleration -- from having to complete earlier or with less time than anticipated, resulting in:

Change In Conditions with Impact

Other

- Additional Overhead -- jobsite or home office for many claims or a specific claim.
- Change Order Preparation and Negotiation Costs -- separate from claim costs.
- Future Costs -- such as higher insurance or workers' compensation premiums.

Markup -- for indirect costs added to direct costs

- Jobsite Overhead -- expressed as a percentage or direct costs.
- Home Office Overhead -- expressed as a percentage of jobsite costs.
- Profit -- expressed as a percentage of total job costs.
- Bond, Insurance Premium and Taxes -- computed as a percent of job cost plus profit.

Below The Line Costs -- added at the end, without markup:

- Retainage and Unpaid Contract Balances
- Interest -- for late payment of retainage, the claimed amounts, or progress payments
- Attorney Fees and Claim Preparation Cost
- Credit for Nonconforming and Unsatisfactory Work

Copyright © 2000 Pinnell♦ Busch, Inc.

UNIT PRICE ESTIMATE

Concrete

100 cy @ \$150/cy =

\$15,000.00

HTGP – Pg. 363

Copyright [©] 2000 Pinnell♦ Busch, Inc.

	Crew and Fo	Productivity r Additional	Rate Estimate Footings		
	No.	Hours	Hourly Base Rate	Subtotal Amount	
1 Labor Daily Rate					
Carpenter foreman	1	8	\$ 18.13	\$ 145.00	
Carpenter journeymen	2	8	16.99 16.70	271.84	
Laborers	4	8	9.45	302.40	
Operating engr. (crane)	<u>1</u> 9 workers	8	16.25	<u>130.00</u> \$ 982.84	
	3 WOIKEIS			φ 302.04	
2. Labor Burden (see Exhib FICA 6.20%	oit A)				
Medicare	1.45				
Federal unemployment Workers' compensation	0.80 7.40				
State unemployment	1.35				
Insurance	0.25				
Labor Burden	18.95 /10	0 x \$982.84		<u>\$186.25</u>	
3. Subtotal Labor Daily Rat	e			\$1,169.09	per day
4. Equipment Daily Rate					
Hyundai Crane, Bucyrus-RT58D	1 day @\$425.00*			\$425.00	per day
Rough Terrain Lift Truck – Bob Rental Rate Blue Book,	's Rentals 13-3			\$300.00	per day
5. Small Tools @ 5% of labor costs	\$1,169.09 x 0.05			\$58.45	per day
DAILY COMPOSITE CR	EW RATE			\$1,952.54	
6. Equipment Daily Rate				\$783.45	per day
7. Estimated Production Ra Form & pour wall estimated @ 50	ate) cy / day (100 cy / 5	50 cy / per day = 2 days)		<u>x 2 days</u>	
9 Matariala (cao Exhibit P)				\$3,905.08	
Form lumber 20 MFBM @ \$240/I	M (invoice attached)			\$2,400.00	
Form Hardware, lump sum estim	. @ 10% of lumber c	ost		240.00	
Consumables @ 3% of l	Ittached) labor.costs\$1.169.09	x = 0.03 = 35.07 / day x 2	davs	4,500.00	
Safety Supplies @ 1% o	f labor costs\$1,169.0	$19 \times 0.01 = 11.96 / day x/$	2 days	23.92	
				\$7,234.06	
9. Subcontract					
R&R Steel quote to furnish and p	l finish concrete (atta lace rebar (attached)	iched)		\$2,000.00 1.275.00	
				\$3,275.00	
10. Recap by Cost Categor	у				
Labor (#3 x 2 days)				\$2,338.18	
Materials (#8)				7,234.06	
Subcontract (#9)				3.275.00	
Subtotal Direct Costs				\$14,414.14	

DELAY DAMAGES

- Extended Jobsite Overhead estimated or from cost accounting records – time dependent costs only
- Extended Home Office Overhead Eichleay formula is applicable only when the contractor cannot obtain other work
- Escalation normally minimal, except for union wage escalation
- Standby of Equipment and Labor
- Under-Utilization of Labor and Equipment
- Subcontractor Demobilization and Re-mobilization
- Labor Layoff and Re-Hire
- Materials Storage, Extra Handling and Deterioration or Theft
- Interest on Retainage and Pending Change Orders
- Extended Warranty Liability
- Lost Profits or Loss of Operating Business
- Ripple Effects of Consequential Delays, Impacts, and Inefficiency
- Inefficiency from Changed Working Conditions e.g. pushing weathersensitive work into winter

Copyright [©] 2000 Pinnell♦ Busch, Inc.

EXTENDED JOBSITE OVERHEAD

General Conditions Item Description Cost per	Work Day
 Field Superintendent 	\$ 340
Carpenter foreman	311
♦ Job Trailer	16
Phone/Pager	17
♦ Fax	8
Copier	10
Weather Service	5
♦ Travel	18
 Storage Trailer 	5
♦ 35 ft 4wd Reach Lift	105
 Two 60 ft Boom Lifts (Ivv HiLift) 	210
♦ 20 Ton Hydro Crane	720
 Forming Material (Mason's Supply) 	429
 Planking Material (Ivv HiLift) 	29
 Safety Equipment (harness, lanvards,) 	50
 Miscellaneous Tools and Equipment 	599
Total Daily Cost	\$ 2,872
The extended jobsite overhead cost is therefore:	
33 days delay @ \$2,872/day =	\$ 94,776

MODIFIED EICHLEAY FORMULA



ACCELERATION DAMAGES

- **Overtime or Shift Work Premium and Fatigue** with resulting inefficiency
- Mobilization and Demobilization additional/larger equipment, more personnel
- Crowding and Trade Stacking
- Excessive Activity Re-sequencing and Overlap with increased conflicts
- Start-Stop Operation and Out-of-Sequence Work
- Additional Tasks e.g. better or additional access roads
- Increased Errors and Rework from rushing, insufficient time for layout, etc.
- Additional Overhead to manage the additional work force
- Overloaded Supervision and Administration more errors and less oversight
- Expedited Materials Delivery vendor premiums, rushed procurement/shipping
- Additional or More Expensive Materials that assemble or install quicker

REASONS FOR LOSS OF EFFICIENCY

- Adverse of Abnormal Environmental Conditions
- Acceleration
- Delay
- Disruption, Interference, And Change
- Inadequate Access and Work Space
- Supervision and Management Problems
- Resource Problems
- Poor Morale
- Safety Constraints
- Errors

Other

Copyright [©] 2000 Pinnell♦ Busch, Inc.

REASONS FOR LOSS OF EFFICIENCY

Adverse or Abnormal Environmental Conditions

♦ Rain

- ♦ Cold
- ♦ Wind
- Combination of Cold, Rain, and Wind together
- ♦ Snow
- ♦ Heat
- ♦ Noise
- Dust or Odors
- Humidity (intensifies effect of heat)
- Poor Lighting or Darkness

Acceleration

- Overtimes
 - Premium labor rates
 - Fatigue physical, mental, boredom
- Multiple Shift Operation
 - Overlap between crews
- Poor lighting
- Circadian rhythm disruption on swing shifts
- Lighting for multi-shift operation
- Shutdown to service equipment
- Shift premium pay
- Rescheduling and Expediting

Delay

- ♦ Idle Labor and Equipment
- Equipment Standby
- Stretch Out/Working at Reduced Pace while waiting for delay to be resolved.

Disruption, Interference, And Change

- ♦ Start-Stop Operation
- Fluctuating Labor Force
- Disruption of Work Flow
- Loss of Learning Curve Effect
- De-Mobilization and Re-Mobilization
- ♦ Out-Of-Sequence Work
- Crew Imbalance
- Frequent Changes
- Uncertainty
- Limited Flexibility
- ♦ Over-Inspection
- Directed Work by Owner

Inadequate Access and Work Space

- Crowding
- Trace Stacking crowding and trade conflicts
- Limited Access
- Inadequate Work Areas for laydown, fabrication or circulation

Supervision and Management Problems

- Dilution of Supervision
- Excessive Supervision
- Poorly Skilled Supervisors
- Increased Supervision
- Overworked Supervisors
- Inadequate Instructions to Crews
- Layout Errors

Resource Problems

- Shortage of Qualified Workers
- Undersized or Insufficient Equipment
- ♦ Excessive Personnel
- Logistics Problems procurement or delivery of materials

Poor Morale

- Uncertainty
- Frustration with Rework
- Absenteeism
- ♦ Theft
- High Turnover
- Deliberate Slowdown

Safety Constraints

- Required Safety Measures
- Caution and Slowdown for dangerous conditions
- Disruption and Slowdown resulting from accident
- Increased Accidents

Errors

- Increased Wastage
- Re-Work
- Increased Clean Up
- Increased Close-Out and Punch List Costs

Other

Additional Materials Handling Multiplicity of Changes

Copyright © 2000 Pinnell♦ Busch, Inc.

METHODS OF COMPUTING INEFFICIENCY

- Expert Opinion and/or Survey
- Total Cost or Cost Plus
- Modified Total Cost adjust for for bid error, contractor mistakes or misfortune (abnormal weather, accidents, etc.)
- Measured Mile adjust for learning curve effect
- Industry Studies charts and formulas
- Scientific Methods work improvement analysis
- Rational Analysis a combination of the above

Copyright © 2000 Pinnell♦ Busch, Inc.

TOTAL COST, MODIFIED TOTAL COST & COST PLUS

TOTAL COST CLAIM:	ACTUAL COST - BID COST
	+ MARKUP
—	
Does not consider bid errors, contractor mistakes, or unfavorable conditions	s. (Seldom used.)
MODIFIED TOTAL COST CLAIM:	ACTUAL COST
	- BID AMOUNT
	- BID ERRORS
	- MISTAKE
	CLAIM AMOUNT
Used when information lacking for using other methods.	

COST PLUS CLAIM:
 ACTUAL COST
 + MARKUP
 CLAIM AMOUNT
 Used when the work performed is materially different from what was bid, so as to constitute a cardinal change and recovery as quantum meruit.

COMMON BID ERRORS

- Quantity Takeoff Errors
- Underestimating Difficulty of the work
- **Underestimating Time** to do the work
- Wrong Assumptions on manner and methods of doing work
- Underestimating Unit Costs of labor, equipment, or materials
- **Forgetting** a work item
- Substitutions -- that assume an "as equal" material quote will be acceptable to the designer

MEASURED MILE

- **1.** Identify Representative Periods of Impacted and Un-impacted Work.
- Determine the Productivity During Each Period in hours or cost per unit of work accomplished using:
 - Weekly Labor Reports from the cost accounting system
 - Monthly Progress Payments Monthly adjust for over/under-billing
 - Other Job Records e.g. crew size and work accomplished on daily reports
 - Videos, Sequential Still Photographs, or Timelapse Photography
 - Historical Records from Similar Projects
 - **Revised Estimates** based on a composite crew and productivity analysis
 - Detailed Work Improvement Analysis
- 3. Adjust the Un-impacted Work for Learning Curve Effects
- 4. Compute the Difference in Productivity
- 5. Compute the Total Loss of Productivity

INDUSTRY STUDIES

- Overtime and Fatigue Bureau of Labor, NECA, Corps of Engineers
- Crowding and Trade Stacking Corps of Engineers
- Overstaffing (Oversided Crews) Corps of Engineers
- Task Reassignment Corps of Engineers
- Multiple Changes the Leonard Study
- **Environmental Conditions** Temperature, Wind, Humidity
- Rain and Show no data available
- Combination of Effects generally not additive



Copyright [©] 2000 Pinnell ♦ Busch, Inc.

LABOR INEFFICIENCY - DIFFERENCE IN VALUE

		Efficiency	
Study	50 hr/wk, %	60 hr/wk, %	70 hr/wk, %
U.S. Bureau of Labor Standards	92	84	78
Foster Wheeler	87	73	
NECA Survey	88	85	78
C.F. Braun	87	73	58
Proctor & Gamble – 12 weeks	84	64	
Proctor & Gamble – 4 weeks	90	84	
U.S. Army MIEG – 4 weeks	96	79	63
Average Value	89%	77%	69%





Copyright [©] 2000 Pinnell♦ Busch, Inc.











HTGP – Pg. 423, Fig.12.11



Copyright © 2000 Pinnell♦ Busch, Inc.